


SITE PLAN w/GRADING, DRAINAGE & EROSION CONTROL PROPOSED BUILDING GROVE DAIRY DISTRIBUTORS, LLC

LOCATED IN PART OF THE NW 1/4 OF THE SW 1/4 OF SECTION 20,
TOWN 3 NORTH, RANGE 21 EAST, RACINE COUNTY, WISCONSIN

GRID NORTH
WISCONSIN STATE PLANE COORDINATE SYSTEM
SOUTH ZONE (NAD-83)
W. LINE OF THE SW 1/4 OF SECTION 19-21 BEARS
N 01°27'52" W



- LEGEND**
- = IRON PIPE FOUND 1 3/8" O.D.
 - = IRON REBAR FOUND 3/4" O.D.
 - ⊙ = WELL LOCATED
 - ☒ = TELEPHONE BOX
 - ▭ = PROPOSED FINISHED GRADE
 - ▭ = RECORDED AS
 - ★ = PROPOSED BLACK HILLS SPRUCE



- SITE INDEX**
- SHEET 1 SITE PLAN w/GRADING, DRAINAGE & EROSION CONTROL
 - SHEET 2 EXTERIOR ELEVATIONS
 - SHEET 3 FIRST FLOOR PLAN
 - SHEET 4 FOUNDATION & STRUCTURAL FRAMING PLANS
 - SHEET 5 BUILDING SECTIONS
 - SHEET 6 BUILDING SECTIONS

SITE SUMMARY

TOTAL LAND AREA 68,800 S.F. 1.58 ACRES
TOTAL AREA DISTURBED 48,900 S.F. (1.12 ACRES) (NOT RECORDED)

SITE SUMMARY

EXISTING BUILDING AREA= 1,490 S.F. 0.04 ACRES 2.2%
EXISTING PAVED AREA= 33,400 S.F. 0.81 ACRES 51.4%
EXISTING GREEN SPACE= 31,900 S.F. 0.73 ACRES 46.4%

PROPOSED BUILDINGS = 8,034 S.F. 0.21 ACRES 13.1%
PROPOSED PAVEMENT AREA = 37,016 S.F. 0.85 ACRES 53.8%
PROPOSED GREEN SPACE AREA = 22,760 S.F. 0.52 ACRES 33.1%




PROPOSED BUILDING
GROVE DAIRY DISTRIBUTORS, LLC
19101 SPRING STREET,
UNION GROVE, RACINE COUNTY, WISCONSIN

SITE PLAN


FARRIS, HANSEN & ASSOCIATES, INC.
ENGINEERING - ARCHITECTURE - SURVEYING
7 MIDCAMPY COURT, P.O. BOX 437
ELKHORN, WISCONSIN 53121
PHONE: (262) 733-3288 e-mail: office@farrishansen.com

REVISIONS
1/25/2024 = SWG
REMOVED TREES AND
REVISIONS




PROJECT NO.
8751.24
DATE
04/17/2024
SHEET NO.
1 OF 6

I:\PROJECTS\8751\8751_24\ACAD\8751_24.dwg




NORTH ELEVATION
SCALE 1/8"=1'-0"

SOUTH ELEVATION
SCALE 1/8"=1'-0"



WEST ELEVATION
SCALE 1/8"=1'-0"



EAST ELEVATION
SCALE 1/8"=1'-0"

PROJECT AND DESIGN DATA	
SITE AREA	= 62,260 SF. OR 157 ACRES
BUILDING AREA	= FIRST FLOOR = 8,004 SF.
CODE	= 2006 INTERNATIONAL BUILDING CODE
CONSTRUCTION TYPE	= V5
OCCUPANCY TYPE	= S-1
GROUND BSW	= 30 psf
WIND VELOCITY	= 85 mph
EXPOSURE CATEGORY	= B
IMPORTANCE FACTOR	= 1.0
OCCUPANCY CATEGORY	= I
SITE CLASS	= 0
SEISMIC DESIGN CATEGORY	= B
FIRE PROTECTION	= NON-SPRINKLERED

DESIGN LOADS	
SOIL BEARING CAPACITY:	
2000 psf ASSUMED SAFE SOIL BEARING PRESSURE. VERIFY W/ GEOTECHNICAL PRIOR TO PLACEMENT OF FOOTINGS.	
ROOF LIVE LOADS:	
ROOF (SLOPE)	= 0
GROUND SNOW LOAD, P _g	= 30 psf
SNOW EXPOSURE OR SNOW LOAD RISK FACTOR	= 1
THERMAL FACTOR	= 1.0 SLOPED ROOF
UNBALANCED SNOW LOAD	= 4/4
FLAT ROOF SNOW LOAD	= 22.5 psf
DRIFTED SNOW LOAD	= SEE ROOF FRAMING PLAN
DECK DEAD LOADS:	
ROOF COLLATERAL	= 3 psf
ROOF DEAD	= 0 psf
DECK WIND LOADS:	
BASIC WIND SPEED (S = 30-MINUTE GUST)	= 115 mph
WIND EXPOSURE FACTOR, K _d	= 1
WIND EXPOSURE CATEGORY	= B
INTERNAL PRESSURE COEFFICIENT	= 0.18
DECK SEISMIC LOADS:	
SEISMIC USE GROUP	= I
SEISMIC DESIGN CATEGORY	= B

GENERAL SPECIFICATIONS
GENERAL REQUIREMENTS

A. DEFINITIONS:
The functions of the construction contract shall be governed by the GENERAL CONTRACTOR. The architect shall not have control or charge of, and shall not be responsible for, construction. Means of methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the work, for the execution or completion of the contract, subcontractors, or any other persons performing any of the work, or for the failure of any of them to carry out the work in accordance with the contract documents. The architect and the contractor shall not be responsible for changes in these documents without written approval and shall have no responsibility for errors and omissions due to dimensions or conditions, details without first being consulted for recommendations and approvals, mistakes.

B. EXAMINATION OF DRAWINGS, SPECIFICATIONS AND SITE:
All bidders shall carefully examine the drawings and specifications prepared for the work. They shall visit the site of the work and acquaint themselves with all local conditions affecting the contract. If awarded the contract, they shall not be allowed any extra compensation by reason of any unforeseen difficulties or obstacles which the bidder could have discovered or reasonably anticipated prior to the bidding.

C. ORDINANCES, RULES AND REGULATIONS:
All work and material covered by the contract documents shall conform to the respective requirements of the latest editions of the following:

A. Standard Specification of the American Society of Testing Materials

B. Provincial and Local Codes, Laws, Ordinances, Rules and Regulations Applicable to the Work.
Ascertain the existence of and comply with any ordinances and/or enforced codes of the STATE AND LOCAL ENFORCEMENT AGENCIES OR INDIVIDUALS peculiar to the area or to the particular installation. Where contract documents call for material or construction of better quality or larger size or greater quantity than required by the above rules and regulations, conform to the provision of the contract documents.

D. INTENT OF DRAWINGS AND SPECIFICATIONS:
Refer to the drawings for all measurements. The measurements given on the architectural plans shall be checked by each subcontractor before proceeding with the work and any discrepancies shall be reported at once to the general contractor. Should it appear that the work covered by the contract documents is not sufficiently detailed or explained, general contractor shall refer to the architect for further drawings or explanations and may be necessary to clarify the point in question. It is the intention of the contract documents to provide a job complete in every respect. General contractor and subcontractors are to be responsible for the need and to form over the project in complete operating condition, irrespective of whether the contract documents cover every individual item in minute detail.

E. QUALITY OF MATERIALS AND WORK:
All work, fixtures, materials and apparatus shall be new in every respect, and it shall be delivered without exception. No brand names shall appear on any of the work in finished building. All work shall be done by those who are thoroughly trained and experienced in that particular trade.

F. SUBCONTRACTOR COOPERATION:
Each subcontractor shall give all notices and comply with all laws, ordinances, rules, regulations and orders of any authority having jurisdiction on the performance of the work under the subcontract. Each subcontractor shall secure and pay for all permits and fees, licenses and inspections necessary for the proper execution and completion of the subcontractor's work.

Each subcontractor shall comply with Federal, provincial and local law laws, codes, security act, unemployment compensation acts and worker's compensation acts insofar as applicable to the performance of the subcontract.

Each subcontractor shall cooperate with the general contractor in scheduling and performing his work to avoid conflict or interference with the work of others.

Each subcontractor shall promptly submit shop drawings and samples by contract document to the general contractor in order to perform his work efficiently, expeditiously and in a manner that will not cause delay in the progress of the work of other subcontractors.

The subcontractor shall give his personal supervisor to the work or have it at the site of the work at all times, a competent and experienced foreman satisfactory to him and the owner, and having authority in full for the subcontractor.

G. WORK OF OTHERS:
Each subcontractor shall take necessary precautions in carrying out his work, to protect properly the finished work of other trades from damage caused by his operations, and shall make good any loss, damage, or injury without cost to the owner.

Each subcontractor shall cooperate with the general contractor and other subcontractors whose work might interfere with the subcontractor's work, and shall participate in the preparation of coordinated drawings in areas of completion as required by the contract documents, satisfactory noting and advising the general contractor of each interference.

H. CHANGES IN WORK:
Each subcontractor may be ordered in writing by the general contractor, without invalidating his subcontract, to make changes in the work within the general scope of his subcontract consisting of additions, deletions, or other revisions. The contract sum and contract time being adjusted accordingly. The subcontractor, prior to the commencement of such changes or revised work, shall submit promptly to the general contractor written copies of all claims for adjustment with the contract documents.

I. CLEANING:
Each subcontractor shall at all times keep the premises free from the accumulation of waste materials or rubbish arising out of the operations of his subcontract. Unless otherwise provided, subcontractor shall not be held responsible for unsafe conditions caused by other subcontractors.

Each subcontractor shall clean all glass, hardware, painted or decorated surfaces, floors, fixtures and equipment to the extent of restoring it to the original finish.

The method and mechanical subcontractors shall be responsible for the cleaning of all of their work, including removal of labels, tags, grease, oil, dirt, etc., etc.

J. GUARANTEE:
Each subcontractor shall guarantee all workmanship and materials entering into the construction of the building for a period of one year after substantial performance, and during the guarantee period, and defects in fully materials are found, he shall immediately, upon notification by the general contractor, proceed at his own expense to bring the work into conformance with the contract documents, together with restoration of fixtures or equipment provided by other trades.

EARTH-WORK

A. Existing Utilities - Locate by hand excavation and provide protection from damage. Coordinate with G.C. and utility companies for re-locating services. Do not break utility connections without notifying G.C. a minimum of 48 hours in advance and providing acceptable temporary service.

B. Flood Damages - To existing utilities as directed by utility company.

C. Site fill and backfill material shall be a granular material free of debris, boulders, organic material and excessive silt.

D. Base fill for slabs on grade shall be a reasonably well graded sand 20% or 30% clean and free of organic material. Compaction shall not exceed 95% in place.

E. Suitable materials obtained for excavation and cutting of the site may be used, if approved by soils ENGINEER.

F. Stockpile excavated material where directed by G.C. until required for backfill and fill.

G. Excavate for structure to elevations and dimensions shown, including excavation a sufficient distance to permit paving and removal of other work and for inspection. The bottom to required free and grade to provide solid base to ready concrete.

H. Excavate for trenches to depth indicated or required and to establish indicated low lines for level elevations. Maintain uniform width required for particular item to be installed, including width to provide ample working room.

Provide 6" to 8" clearance on both sides of pipe or conduit. Outside building excavate trenches for water bearing piping as top of piping to base of roof level where applicable, as per local building codes/official.

L. Remove existing walls, drives, curbs, foundations, columns, boulders, vegetation (trees, stumps and roots) or larger in diameter than the base of the building's System, basins, and similar items as necessary to execute the work of the project.

J. Notify the G.C. if abnormal or questionable soil conditions are encountered, and do not proceed with the work until directed by the G.C.

K. Maintain excavations in a clean condition and keep free of water at all times. Protect bottom of excavations from frost and freezing. Do not excavate to full depth during freezing weather unless bottom or side can be poured immediately after completion of excavation work, and protect walls to prevent freezing after footing and slab have been poured.

L. Do not use frozen material or material containing ice or snow for fill. Do not place on work that is frozen or covered with ice or snow. Take necessary precautions during freezing weather to prevent freezing of fill during placing and compaction.

M. Place all fill materials in 6" layers, compacting each layer to require maximum density unless otherwise recommended in the approved soil report on record with G.C. Keep compacted fill relatively smooth and level.



PROPOSED BUILDING
GROVE DAIRY DISTRIBUTORS, LLC
1801 SPRING STREET
UNION GROVE, WISCONSIN

EXTERIOR ELEVATIONS
GENERAL SPECIFICATIONS


FARRIS, HANSEN & ASSOCIATES, INC.
Engineering, Architecture, Surveying
7 Highway Court, P.O. Box 437
Eau Claire, WISCONSIN 54601
Office: (608) 723-2068
Fax: (608) 723-5886

REVISIONS


RECEIVED
AUG 27 2024
RACINE COUNTY

PROJECT NO.
875124
DATE
04/10/2024
SHEET NO.
2 of 6


HANDICAP DETAILS



HANDICAP PARKING SIGN





HANDICAP LAVATORY CLEARANCES



WATER CLOSET HANDICAP GRAB BAR LOCATIONS

TOILETROOM ACCESSORIES



FIRST FLOOR PLAN



CEILING ROOF SYSTEM
 28 GA. GALVALUME STEEL FRAMING ROOF
 2x4 PURLIN @ 24" O.C. (ON SELECT STRUCTURAL)
 2x8 JOIST @ 24" O.C. (ON SELECT STRUCTURAL)
 2" MINIMUM INSULATION R-19
 2" BLOWN-IN INSULATION R-19
 5/8" DRYWALL CEILING

CEILING WALL SYSTEM
 28 GA. GALVALUME STEEL WALL PANELS
 2x4 STUDS @ 24" O.C. (ON SELECT STRUCTURAL)
 2x8 JOIST @ 24" O.C. (ON SELECT STRUCTURAL)
 2" MINIMUM INSULATION R-19
 2" BLOWN-IN INSULATION R-19
 5/8" DRYWALL

- N. Base RI compaction within the lines of new building and site fill and basalt liner pavement exposures. To be as recommended by sole ENGINEER. Excavate as necessary to remove all organic soils and loose existing fill, and fill to grade, compacting each lift of base fill according to the recommendation of the sole ENGINEER. Provide same method of compaction at all mechanical trenches and other similar areas.
- O. Provide minimum 6" uncracked base under all slab-on-grade, unless otherwise noted or as recommended by approved sole report.
- P. Foundations were designated using a soil bearing value of 2000 psf as listed in the structural design where noted or as recommended by sole ENGINEER. The sole ENGINEER shall confirm in writing the value obtained in the field.
- CAST-IN-PLACE CONCRETE
- A. CODES AND STANDARDS: ACI 301, ACI 308 comply with applicable provisions except as otherwise indicated.
- B. MIX PROPORTIONS AND DESIGN: Proportion mixes by either laboratory trial batch or field experience method complying with ACI 301.
- C. CONCRETE MATERIALS: Portland cement - ASTM C 150, type I structural notes. Aggregates - ASTM C 33. Water - Clean, Drinkable. Air-Entraining Material - ASTM C 260.
- D. REINFORCING MATERIALS: Deformed reinforcing bars - ASTM A 615, Grade 40 unless otherwise indicated. Waxed wire fabric - ASTM A 185.
- E. CONCRETE PLACEMENT: Hot and cold weather comply with ACI 308.
- F. CONCRETE STRENGTH: Concrete strength to be 4000 psi in 28 days. slump not exceed 4 inches.
- G. COVER ON REINFORCING STEEL: Cover on reinforcing steel to be 3 inches next to ground, 2 inches next to wall forms. Lap reinforcing steel bars 24 bar diameters minimum and lap mesh 6 inches minimum.
- H. FINISHES AND CURING CONCRETE: Surfaces exposed to view: Provide smooth finish, remove line and projections, patch defective areas with cement grout. Sidewalks: Broom finish. Curing: Begin initial curing as soon as free water has disappeared from exposed surfaces. Where possible, keep continuously moist for not less than 72 hours. Continue curing by use of moisture-retaining cover or curing compound. Cure formed surfaces by moist curing until forms are removed. Keep wall forms in 24 hours before stripping. Provide protection as required to prevent damage to exposed concrete surfaces.
- MASONRY - SEE DRAWINGS.
- A. Colored stone veneer to be furnished by GC installed by subcontractor. Color to be selected by OWNER.
- B. Colored stone veneer to be installed over 1/2" GOS board sheathing and installed per manufacturer requirements.
- CARPENTRY
- A. GENERAL: All construction shall be done in accordance with Wisconsin Admin. Code, Section INS 53.01.
- B. MATERIALS: 1. Lumber: Comply with American Softwood Lumber Standard (PS 20), U.S. Dept. of Commerce, 5845, 10C, moisture at the time of drying. 2. Plywood: Comply with Softwood Plywood - Construction and Industrial (PS 1), U.S. Dept. of Commerce, bearing DFPA grade trademarks. 3. Pre-engineered Roof Trusses: a. Building shall have a gable roof and wood trusses - trusses shall be designed for a 10 psf dead load in addition to a 20 lb. snow load and a 20 lb. wind load. Roof load shall be provided for with a 10% stress adjustment for snow load duration and all necessary additional snow drift loads. b. Truss construction shall be in conformance with approved truss diagrams, load computation and fabrication details forwarded by the truss manufacturer. 4. Truss manufacturer shall provide architect/engineer with a minimum of 3 sets of an electronic copy of truss computations and diagrams for review and submittal to the State for approval. 5. Walls: a. EXTERIOR: 2x6 laminated posts @ 24" o/c and 2x6 exterior girts @ 24" o/c max. and 2x4 interior girts @ 24" o/c. All lumber in contact with concrete shall be pressure treated. b. INTERIOR: 2 x 4 studs 16" o/c, with 1/2" drywall each side. 6. MOISTURE PROTECTION: A. BLANKET INSULATION: Ball or continuous blanket of thickness indicated, unfastened with 4 mil polyethylene vapor barrier. 7. RIGID INSULATION: Polyethylene insulation not less than 25 psi compressive strength for all vertical insulation and min. of 60 psi for all horizontal insulation. 8. VAPOR BARRIER: Clear polyethylene sheathing, 4 mils thick. 9. SILL SEALER: T neek fiberglass seal to be installed beneath all sills/pine at exterior walls. 10. ROOFING: 28 GA. MELLOY R-panel metal roof panels on 2 x 4 purlins 24" o/c. 11. EXTERIOR SIDING: 28 GA. MELLOY R-panel metal wall panels on wall girts 24" o/c. 12. EXTERIOR TRIMS: All corner, window, fascia, rafter, soffit and accent trim to be steel or aluminum as indicated on plans. All trim to be pre-treated. Soffit panels to be perforated for ventilation. Color to be selected by Owner. 13. SHEET METAL WORK: a. Flashing & Drip Caps: Paint, galv - Zinc coated sheet steel. Commercial quality galvanized steel sheets with minimum 0.25% copper content (ASTM A 596), hot-dip galvanized (ASTM A 593), G90, 22 gauge unless otherwise indicated. b. CALLING AND SEALANTS: Scope of Work: Caulk side jacks, sills and heads of all windows, side jacks and heads of all exterior door wood frames, side jacks and heads of all hollow metal frames, masonry expansion joints and all joints where dissimilar materials meet, and caulking is noted on the drawings and/or required to seal building against weather. Provide all necessary metal flashing. FINISHES: A. SUB-BASE MATERIALS: 1. Gypsum Drywall: ASTM C 36, except ASTM C 482 permitted for base layers. Provide boards with top edges tapered for joint finish treatment. B. PAINTING: 1. INTERIOR FINISHES: A. All gypsum board to receive one (1) coat sand/finish textured paint as base coat and one (1) final coat. B. All units shall be painted with one coat. Solid color latex paint to be approved by Owner. Color to be selected by Owner. C. TOILET ROOM FLOORS: The entire floor and side walls to a height of not less than 6 inches shall be made waterproof with ceramic tile, terrazzo, painted concrete or other approved material impervious to water. D. WINDOWS: 1. EXTERIOR: JELD-WEN or Equal insulated glass sliding windows in vinyl frames. 2. INTERIOR: 1/4" single pane tempered glass in aluminum frames.




PROPOSED BUILDING
GROVE DAIRY DISTRIBUTORS, LLC
 1001 SPRING STREET
 UNION GROVE, RACINE, CO., WISCONSIN

FIRST FLOOR PLAN
 GENERAL SPECIFICATIONS
 HANDICAP DETAILS


FARRIS, HANSEN & ASSOCIATES, INC.
 Engineering, Architecture, Surveying
 7 Riverside Court, P.O. Box 497
 ELKHORN, WISCONSIN 53121
 O/Res: (262) 723-2068
 Fax: (262) 723-5886

REVISIONS





PROJECT NO.
 875124
 DATE
 04/16/2024
 SHEET NO.
 3 of 8


WALL TYPES



SCREW FASTENER POSITIONS




PURLIN LAP DETAIL



FOUNDATION PLAN

FOOTING SCHEDULE

- 30" DIA. BORE HOLE W/ 30" DIAM⁸ PRECAST CONG. FTG. TOP OF FTG 48" BELOW GRADE
- 18" DIA. BORE HOLE W/ 18" DIAM⁸ PRECAST CONG. FTG. TOP OF FTG 48" BELOW GRADE
- 24" DIA. BORE HOLE W/ 24" DIAM⁸ CONCRETE FTG. TOP OF FTG 48" BELOW GRADE
- 26" DIA. BORE HOLE W/ 26" DIAM⁸ CONCRETE FTG. TOP OF FTG 48" BELOW GRADE



ROOF TRUSS SCHEDULE

- TYPE T1 = PRE-ENGINEERED ROOF TRUSSES 60' SPAN 8'-0"oc, 3/2 ROOF PITCH, 24" OVERHANG EACH SIDE
- TYPE T2 = PRE-ENGINEERED ROOF TRUSSES 42' SPAN 8'-0"oc, 3/2 ROOF PITCH, 24" OVERHANG EACH SIDE
- TYPE T3 = PRE-ENGINEERED ROOF TRUSSES 42' SPAN 8'-0"oc, 3/2 ROOF PITCH, 24" OVERHANG EACH SIDE
- TYPE T4 = PRE-ENGINEERED ROOF TRUSSES 6'-6" SPAN 24'oc, 3/2 ROOF PITCH, 24" OVERHANG EACH SIDE

STRUCTURAL FRAMING PLAN

HEADER SCHEDULE

- TYPE H1 = 2-2x0 SOUTHERN PINE NO.1
- TYPE H2 = 2-2x2 SOUTHERN PINE NO.1 DENSE

COLUMN SCHEDULE

- TYPE C1 = 3 PLY 2x8 LAMINATED WOOD COLUMN
- TYPE C2 = 3 PLY 2x6 LAMINATED WOOD COLUMN
- TYPE C3 = 4 PLY 2x6 LAMINATED WOOD COLUMN W/ 1' CEDAR WRAP



PROPOSED BUILDING
GROVE DAIRY DISTRIBUTORS, LLC
1801 SPRING STREET
UNION GROVE, RACINE CO., WISCONSIN


FOUNDATION PLAN
STRUCTURAL FRAMING PLAN
WALL TYPES, DETAILS

FARRIS HANSEN & ASSOCIATES, INC.
Engineering Architecture Surveying
7 Prairie Court P.O. Box 497
Eau Claire, WISCONSIN 54601
Office: (608) 733-2068
Fax: (608) 733-2888


RECEIVED
AUG 27 2024
RACINE COUNTY

PROJECT NO.
875124
DATE
04/10/2024
SHEET NO.
4 of 8

Tuesday, May 7, 2024



BUILDING SECTION 2
SCALE 3/8"=1'-0"



BUILDING SECTION 1
SCALE 3/8"=1'-0"

PROPOSED BUILDING
DARY DISTRIBUTORS, LLC
 GROVE SPRING STREET
 UNION GROVE, RACINE CO., WISCONSIN

SECTIONS


FARRIS, HANSEN & ASSOCIATES, INC.
 Engineering, Architecture, Surveying
 7 Highway Court, P.O. Box 487
 Elkhorn, WI 53121
 Phone: (262) 753-2088
 Fax: (262) 753-5888

REVISED

RECEIVED
 AUG 27 2024
 RACINE COUNTY

PROJECT NO
 875124
 DATE
 04/16/2024
 SHEET NO
 5 of 8

Tuesday, May 7, 2024
C:\projects\2024\875124\FINALS\FINAL_SECTION3.rvt



BUILDING SECTION 3
SCALE 3/8"=1'-0"




PROPOSED BUILDING
GROVE DAIRY DISTRIBUTORS, LLC
1801 SPRING STREET
LUNDEN GROVE, WISCONSIN


SECTIONS

FARRIS, HANSEY & ASSOCIATES, INC.
Engineering, Architecture, Surveying
7 Ridgway Court P.O. Box 407
Elm Grove, WI 53121
Office: (262) 722-2026
Fax: (262) 722-5888

REVISIONS



PROJECT NO	875124
DATE	04/18/2024
SHEET NO	8 of 8



PROPOSED BUILDING
GROVE DAIRY DISTRIBUTORS, LLC
 19101 SPRING STREET
 UNION GROVE, RACINE CO., WISCONSIN

FIRST FLOOR PLAN
 GENERAL SPECIFICATIONS
 HANDICAP DETAILS


FARRIS, HANSEN & ASSOCIATES, INC.
 Engineering, Architecture, Surveying
 7 Ridgeway Court, P.O. Box 437
 ELKHORN, WISCONSIN 53121
 Office: (262) 729-2088
 Fax: (262) 729-5888



Grove Dairy Distributors
 Union Grove, WI
 Overhead Door and Mandoor Exterior Illumination

RECEIVED
 AUG 27 2024
 RACINE COUNTY

Designer
S. Schoenberger
 Date
 8/22/2024
 Scale
 Not to Scale
 Drawing No.
 11:50 AM
 Summary



ROOF
 28 GA. GALV. STEEL R-19 PANEL ROOF
 2x4 PLYWOOD 24" OC (1 OF NO. 1)
 PRE-ENGINEERED ROOF TRUSSES # 8-0" OC
 1/2" BLOWN-IN INSULATION R-30
 28 GA. GALV. STEEL R-19 PANEL CEILING

CEILING WALL SYSTEM
 CULTURED STONE OR 28 GA. STEEL WALL PANELS
 2x6 EXTERIOR GITS # 24" OC (PLAT)
 2x6 UNPAINTED WOOD CEILING
 1/2" FIBERGLASS BATT INS. (R-30)
 2x4 EXTERIOR GITS # 24" OC
 5/8" DRYWALL

FIRST
 SCALE 1/8"=1'-0"

N Base fill compactor (within the area of new building) and fill (fill and backfill under pavement subgrade) - To be as recommended by site ENGINEER. Excavate as necessary to remove all organic soils and loose existing fill and fill to grade, compacting each lift of case fill according to the recommendation of the site ENGINEER. Provide same method of compaction of all mechanical trenches and other similar areas.

C Provide minimum 6" sand/gravel base under all non-concrete, unless otherwise noted or as recommended by approved site report.

H FINISHES AND CURING CONCRETE
 Surfaces exposed to view: Provide smooth finish, remove lint and projectors, patch defective areas with cement grout.
 Sidewalks: Brush finish.
 Curing: Begin initial curing as soon as free water has disappeared from exposed surfaces. Where possible, keep continuously moist for not less than 72 hours. Continue curing by use of moisture-retaining cover or curing compound.

Symbol	Label	Stage	QTY	Manufacturer	Catalog	Description	Quantity	Unit	LLP	Unit Price	Notes
CA	B		1	EXTRONIX, A DIVISION OF BARON LIGHTING GROUP	TR1-AC - TRITON GENERAL LIGHTING	WITH WHITE INTERIOR AND CURVED PRISMATIC PLASTIC LENS	385	0.95	15		
B			2	RAB Lighting Inc.	SLM179AFCD10_4K at 0% CCT Setting		14964	0.95	102.77		Max: 179cd Max: 6125cd

Statistics

Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
West Side Man Door EXTERIOR Illumination	+	2.3 fc	2.9 fc	1.7 fc	1.7:1	1.4:1
Overhead Door EXTERIOR Illumination	+	8.6 fc	24.7 fc	1.0 fc	24.7:1	8.6:1

D. REINFORCING MATERIALS
 PS 20 US Dept of Commerce S48 10% moisture at the time of casting

F. EXTERIOR SIDING
 28 GA. MELBROY R-panel metal wall panels or wall girts 24" o/c

G. EXTERIOR TRIMS

C. TOILET ROOM FLOORS
 The entire floor and side walls to a height of not less than 6 inches shall be made waterproof with organic tile, terrazzo painted concrete or other approved material impervious to water.

WINDOWS