

ADVERTISEMENT FOR BIDS

Yorkville Well #2
Village of Yorkville, Wisconsin
SEH No. YORSU 169862

Notice is hereby given that Online Bids will be received by the by the Village of Yorkville until **2:00 p.m. Local Time, July 30, 2024** via QuestCDN, for the furnishing of all labor and material for the construction of the following items in the approximate quantities indicated:

| Quantity | | Item |
|---|-------|---|
| <i>Phase 1 Exploratory Drilling</i> | | |
| 1 | L.S. | Mobilization/Demobilization |
| 177 | L.F. | Furnish, Drill, and Drive 20" Diameter Casing & Hole |
| 1 | L.S. | Plumbness and Alignment Testing |
| 177 | L.F. | Furnish and Install 8" Steel Casing with Centralizers |
| 1523 | L.F. | Drill & Drive 8" Open Hole |
| 1 | L.S. | Logging |
| 1 | L.S. | Furnish, Install, & Remove Test Pump |
| 24 | Hours | 24-hour Test |
| 1 | L.S. | Water Quality Testing |
| <i>Phase 2 Production Well</i> | | |
| 1 | L.S. | Remove 8" Steel Working Casing |
| 477 | L.F. | Ream 8" Pilot Hole to 19" Hole (117' to 594') |
| 1 | L.S. | Plumbness & Alignment Testing |
| 594 | L.F. | Furnish, Drill, and Drive 16" Diameter Casing (to 594') |
| 1 | L.S. | Remove 20" Steel Working Casing |
| 1 | L.S. | Furnish Grout Equipment |
| 838 | Sacks | Cement |
| 1106 | L.F. | Drill & Drive 15" Open Hole (594' to 1700') |
| 40 | Hour | Develop Well |
| 24 | Hour | Step-Drawdown Test |
| 72 | Hour | 72-hour Constant Rate Test |
| 1 | L.S. | Water Quality Testing |
| 1 | L.S. | Televise |
| 1 | L.S. | Demobilization |
| 1 | L.S. | Pitless Adaptor |
| 1 | L.S. | Submersible Well Pump |
| <i>Connection to Existing Chemical Feed and Monitoring Building Piping</i> | | |
| 1 | L.S. | All Work Not Otherwise Listed Separately, Including: |
| | | Installation of raw water main and appurtenances |
| | | Installation of process piping, valves and meter |
| | | Electrical and controls improvements |
| | | New backup generator |
| | | Miscellaneous site restoration |

